table1 project segment counts

Dimension	Category	All data				Analysis sample (N=3)				Analysis sample (N=5)				Analysis sample (N=6)			
		Projects	Segments	AADT obs.	Projects w/ open date	Projects	Segments	AADT obs. used	Mean % change	Projects	Segments	AADT obs. used	Mean % change	Projects	Segments	AADT obs. used	Mean % change
All	All data	176	549	6,079	93	52	150	729	2.6	56	169	1,153	5.7	60	175	1,325	5.7
State	KY	104	285	3,155	23	19	33	90	1.3	20	44	175	2.8	20	45	205	4.1
State	MN	43	149	1,273	43	18	69	361	-2.2	18	69	512	-1.0	18	69	533	-0.7
State	FL	25	71	1,244	25	14	47	275	10.3	17	53	456	16.5	21	58	574	12.9
State	NY	2	16	257	1	0	0	0	-	0	0	0	-	0	0	0	-
State	NH	1	19	100	0	0	0	0	-	0	0	0	-	0	0	0	-
State	NE	1	9	50	1	1	1	3	8.7	1	3	10	2.8	1	3	13	-1.0
Project type	Capacity expansion (widening)	176	549	6,079	93	52	150	729	2.6	56	169	1,153	5.7	60	175	1,325	5.7
Area type	Urban	69	210	2,525	32	19	59	310	5.0	20	66	503	6.6	24	71	621	6.0
Area type	Suburban / exurban	14	84	675	14	8	37	187	-1.9	8	37	270	-1.0	8	37	278	-0.6
Area type	Rural	90	252	2,853	44	25	54	232	2.3	28	66	380	7.1	28	67	426	7.1
Area type	Unknown	3	3	26	3	0	0	0	-	0	0	0	-	0	0	0	-
Opening period	1999 or earlier	15	21	220	15	0	0	0	-	0	0	0	-	0	0	0	-
Opening period	2000-2009	16	35	432	16	3	8	24	-8.4	6	11	45	12.7	9	16	83	10.6
Opening period	2010-2015	14	40	572	14	9	22	113	7.7	10	26	175	10.7	11	27	204	8.7
Opening period	2016-2019	25	74	1,003	25	21	57	302	0.3	21	64	493	2.0	21	64	577	2.2
Opening period	2020 or later	23	119	1,081	23	19	63	290	4.6	19	68	440	5.1	19	68	461	5.4
Opening period	No open date	83	260	2,771	0	0	0	0	-	0	0	0	-	0	0	0	-
Facility type (segment level)	Interstate / freeway / expressway	25	58	863	18	11	19	-	8.7	11	22	-	7.8	11	22	-	8.2
Facility type (segment level)	Principal arterial	58	147	1,796	49	25	70	-	5.1	26	75	-	8.0	29	78	-	8.1
Facility type (segment level)	Minor arterial	30	67	694	17	12	29	-	-3.1	13	31	-	0.4	13	31	-	0.5
Facility type (segment level)	Collector	12	18	160	6	2	3	-	5.6	2	5	-	6.8	2	5	-	5.0
Facility type (segment level)	Ramp	8	47	296	8	3	18	-	-17.0	3	18	-	-14.2	3	18	-	-14.2

Dimension	Category	All data				Analysis sample (N=3)				Analysis sample (N=5)				Analysis sample (N=6)			
		Projects	Segments	AADT obs.	Projects w/ open date	Projects	Segments	AADT obs. used	Mean % change	Projects	Segments	AADT obs. used	Mean % change	Projects	Segments	AADT obs. used	Mean % change
Facility type (segment level)	Local	1	1	10	0	0	0	-	-	0	0	-	-	0	0	-	-
Facility type (segment level)	Unknown	69	211	2,260	15	5	11	-	5.5	8	18	-	9.0	9	21	-	7.7
Point of Interest	Added through lanes	69	128	1,749	38	29	61	-	10.7	33	73	-	12.9	33	74	-	13.2
Point of Interest	Added left turn lanes	14	19	228	13	7	10	-	-4.1	10	13	-	1.8	10	13	-	-0.7
Point of Interest	Added right turn lanes	7	10	108	6	2	3	-	-12.2	4	5	-	-5.4	4	5	-	-4.9
Point of Interest	Improved shoulder width	26	50	779	26	20	39	-	5.9	21	41	-	8.0	24	45	-	7.1
Point of Interest	Improved lane width	40	67	820	27	17	33	-	6.1	19	35	-	9.2	22	39	-	9.7