table1 project segment counts

Dimension	Category	All data				Analysis sample (N=3)				Analysis sample (N=5)				Analysis sample (N=6)			
		Projects	Segments	AADT obs.	Projects w/ open date	Projects	Segments	AADT obs. used	Mean % change	Projects	Segments	AADT obs. used	Mean % change	Projects	Segments	AADT obs. used	Mean % change
All	All data	156	511	5,712	154	127	323	1,190	2.8	137	372	2,008	4.5	141	382	2,346	4.3
State	KY	104	285	3,155	104	94	206	551	2.6	101	247	1,030	3.5	101	252	1,226	3.4
State	FL	25	71	1,244	25	14	47	275	10.3	17	53	456	16.5	21	58	574	12.9
State	MN	23	111	906	23	18	69	361	-2.2	18	69	512	-1.0	18	69	533	-0.7
State	NY	2	16	257	1	0	0	0	-	0	0	0	-	0	0	0	-
State	NH	1	19	100	0	0	0	0	-	0	0	0	-	0	0	0	-
State	NE	1	9	50	1	1	1	3	8.7	1	3	10	2.8	1	3	13	-1.0
Project type	Capacity expansion (widening)	156	511	5,712	154	127	323	1,190	2.8	137	372	2,008	4.5	141	382	2,346	4.3
Area type	Urban	66	203	2,458	64	51	118	439	4.7	55	139	746	7.1	59	146	920	6.6
Area type	Suburban / exurban	11	70	550	11	8	37	187	-1.9	8	37	270	-1.0	8	37	278	-0.6
Area type	Rural	79	238	2,704	79	68	168	564	2.0	74	196	992	3.3	74	199	1,148	2.9
Area type	Unknown	0	0	0	0	0	0	0	-	0	0	0	-	0	0	0	-
Opening period	1999 or earlier	0	0	0	0	0	0	0	-	0	0	0	-	0	0	0	-
Opening period	2000-2009	42	123	1,439	42	32	86	226	0.0	37	99	418	2.3	40	106	525	1.2
Opening period	2010-2015	44	124	1,478	44	36	84	281	5.0	40	99	486	6.3	41	102	586	5.6
Opening period	2016-2019	42	113	1,465	42	37	85	381	2.6	38	101	649	4.8	38	101	757	5.4
Opening period	2020 or later	26	126	1,129	26	22	68	302	3.7	22	73	455	4.8	22	73	478	5.4
Opening period	No open date	2	25	201	0	0	0	0	-	0	0	0	-	0	0	0	-
Facility type (segment level)	Interstate / freeway / expressway	21	46	768	20	18	31	-	8.4	18	35	-	9.0	18	35	-	9.8
Facility type (segment level)	Principal arterial	50	137	1,684	49	33	86	-	4.6	34	93	-	6.7	37	96	-	6.9
Facility type (segment level)	Minor arterial	33	74	761	32	25	51	-	-0.3	28	59	-	3.4	28	59	-	4.0
Facility type (segment level)	Collector	10	14	119	9	6	7	-	2.3	8	11	-	5.0	8	11	-	4.6
Facility type (segment level)	Ramp	6	44	276	6	3	18	-	-17.0	3	18	-	-14.2	3	18	-	-14.2

Dimension	Category	All data				Analysis sample (N=3)				Analysis sample (N=5)				Analysis sample (N=6)			
		Projects	Segments	AADT obs.	Projects w/ open date	Projects	Segments	AADT obs. used	Mean % change	Projects	Segments	AADT obs. used	Mean % change	Projects	Segments	AADT obs. used	Mean % change
Facility type (segment level)	Local	1	1	10	0	0	0	-	-	0	0	-	-	0	0	-	-
Facility type (segment level)	Unknown	60	195	2,094	59	50	130	-	3.4	56	156	-	3.0	57	163	-	2.6
Point of Interest	Added through lanes	71	130	1,783	71	55	100	-	9.2	65	122	-	11.2	66	124	-	11.4
Point of Interest	Added left turn lanes	14	19	228	14	8	12	-	-3.2	11	15	-	0.1	11	15	-	-2.0
Point of Interest	Added right turn lanes	7	10	108	7	3	5	-	-6.9	5	7	-	-6.9	5	7	-	-6.5
Point of Interest	Improved shoulder width	26	50	779	26	20	39	-	5.9	21	41	-	8.0	24	45	-	7.1
Point of Interest	Improved lane width	41	68	831	41	29	48	-	4.8	33	57	-	7.9	36	61	-	8.7